



Village of Quogue Driveway Apron Standards

New and replaced driveway aprons in a public or private right-of-way must meet the edge of the road surface in order to protect the roadway from damage. Aprons shall be constructed to the following standards:

1. A stabilized soil sub-base shall be provided.
2. Install six inches of RCA or equivalent base material.
3. Four inches Type 6 asphalt hot mix or six inches of concrete (3500 PSI at 28 days minimum) reinforced with 6" x 6" wire mesh.
4. Aprons shall be constructed of asphalt, concrete, or cobblestone.
5. The width of the apron at the edge of the road shall be a minimum of twelve feet to eighteen feet maximum. The apron shall be above the top of the existing pavement by no more than three inches beginning at six feet off the edge of the road.
6. Aprons shall provide a minimum depth off of the road edge of eighteen inches with asphalt (sealed to the road edge) matching the existing road surface.
7. The apron shall conform to the profile of the existing gutter line of the roadway and right-of-way to allow passage of stormwater drainage.
8. All aprons shall be constructed curbless within the first six feet of the road edge. Aprons shall be constructed so as to not obstruct road maintenance and snow removal.
9. The profile of the apron shall have a minimum pitch out of the road of ½" inch per foot to prevent storm water from entering the road. The apron shall pitch from the high point of the driveway a minimum of ¼" per foot.
10. Any grading, planting or installation of shrubbery in the right-of-way shall have prior approval from the Highway Department.
11. Installers are responsible to ***"Call Before You Dig"*** 811 or 1-800-272-4480.

